

I/32011/2022

## Annexure -'A'

SCHEDULE OF TENDER /QUOTATIONDetails specification for Development of Display Gallery at 1<sup>st</sup> floor, Archaeological Museum, Itafort.

Sl. No.	Description of Work	Qty	Unit	Rate to be Quoted including GST etc. Per Unit	Remarks
1	<b>False Ceiling:</b> Providing and fixing Grid Ceiling with designer cut and breaks in levels and forms, made of standard G.I.Sections and gyproc board sheets inclusive of all hangers,edge members and other clips complete,with sheets fixed with proper screws by power drills and joints duly finished ensuring level in line to take final paint.(Make: SAINTGOBAIN Gyproc Ceiling Solution/LA GYP	925	Sq. ft.		
2	<b>Painting &amp; POP works on Ceiling:</b> Providing and applying three coats of pre-approved acrylic emulsion paint including surface preparation and sanding all complete. Providing and applying punning to the surface required punning to be undertaken and completed in work man-like manner, to ensure desired finishing standards, (ASIAN PAINTS/ NEROLAC/ BERGER)	1176	Sq. ft.		
3	<b>Flooring:</b> Providing,SupplyingandLayingofWoodenPlanksFlooringintheentire CarpetAreaRoom.(Make:ARMSTRONG/ WONDERFLOOR)	864	Sq. ft.		
4	<b>Showcases ,Pedestal and Table Top Display:</b>				
	a) Corner Display Showcases-Sizes :4'x4'x2'x6'	2	Per Nos.		
	b) Table Top Showcase- Sizes :4.6'x2'x2.7'	2	Per Nos.		
	c) Display Showcases- Sizes:7'x2'x6'	4	Per Nos.		
	d) Table Top Display - Sizes :2'x2'x2.6'	4	Per Nos.		
	e) Table Top Padestal- Sizes :1.6'x1.6'x2.9'	6	Per Nos.		
5	<b>Electrifications with Concept Lighting:</b> Complete Wiring with(RR Kabel/Havell's) Wire 1mm,1.5mm.Switches(RR Kabel /Havell's)Flour scent Light /Ultra Violet Resistance Light(Philips/Havell's)	1 Job			
	a) Ultra Violet Resistance Light for Showcases	14	Per Nos.		
	b) Spot & Room Lighting	12	Per Nos.		
	c) Wiring, Switches & other Accessories with assembling	1	Per set		
6	<b>Partitions/ Paneling:</b> Providing and fixing full height solid partitions paneling with themes and designs, framing with salwood and fixing waterproof ply.	194	Per Sq. ft.		
7	<b>Granule Works:</b> Granules Finish with Master Builders' as per themes and design.	364	Sq. ft.		
8	<b>Display and Labeling Works:</b> Display – displaying artefacts in the showcases and labeling with their description in printing form and fixing with acrylic sheet/ polished glass	1 Job			
9	<b>Table for Research Work at Laboratory:</b> Customized table for the Laboratory (3x10) size – Providing, making and fixing customized table with 19 mm waterproof ply, veneer/ laminates, teak wood, molded teak wood bit, and other accessories as per approved design.	1	Per Nos.		

I/32011/2022

10	<b>Chairs for Laboratory:</b> Supplying & Providing of Laboratory Chairs & door fitting	6	Per Nos.		
11	<b>Digital Environment Corner:</b> Supplying, Providing and Installing of a Digital Media with HD output & Dolby Surround Sound with a movie/Media Presentation on the Archaeological sites of the state maintaining a sequence and running with continuous in loop through digital HD output media	1	Per Set		
12	<b>AC fitting :</b> Supplying, Providing and AC fitting in 2 <sup>nd</sup> floor . (1.5 Ton godrej / L.G)	2	Per Nos.		
13	Steel Book shelf ( Steel & style) for storage of Chemicals and Laboratory equipments	2	Per Nos.		

(Kanggo Tayeng)  
Director of Research  
Govt. of A.P., Itanagar